

BID AWARD SUMMARY

LETTING DATE: June 13, 2017

PROJECT: Pavement Rehabilitation Project - Powderhorn Drive
Project No. 17-2376 / CIP No. 50549

RECOMMENDATION: Award Total Bid in the amount of \$174,892.10 to Western Construction, Inc. at the June 19, 2017 Council Meeting.

BIDDERS' SUMMARY

<u>CONTRACTORS</u>	<u>TOTAL BID</u>
Western Construction, Inc.	\$174,892.10
J & J Asphalt	\$202,535.50
Hills Materials Company	\$224,479.20


City staff recommends awarding this project to Western Construction, Inc. for the total bid amount of \$174,892.10 based on unit pricing with the following appropriation:

FUNDING SOURCE	TOTAL	Streets
ADVERTISING AUTHORITY	\$250,000.00	\$250,000.00
ENGINEER'S ESTIMATE	\$235,000.00	\$

APPROPRIATION DATA:

FUNDING SOURCE	TOTAL	Streets
COST CENTER		8910
LINE ITEM		4370
FUNDING CENTER		505
BID AMOUNT	\$174,892.10	\$174,892.10

PROJECT MANAGER:


Todd Peckosh, PE
City of Rapid City

DATE:

6/14/17

PROJECT NAME: Pavement Rehabilitation Project - Powderhorn Drive

PROJECT NUMBER: PROJECT NO. 17-2376 / CIP NO. 50549

LET DATE: June 13, 2017

LOW BID AMOUNT: \$174,892.10

ITEM NO.	STD. BID ITEM NO.	DESCRIPTION OF ITEM	UNIT	QTY (EST)	ENGINEER'S ESTIMATE		WESTERN CONSTRUCTION, INC.		J & J ASPHALT		HILLS MATERIALS COMPANY	
					UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
1		Mobilization	LS	1.00	\$12,645.00	\$12,645.00	\$4,775.00	\$4,775.00	\$6,000.00	\$6,000.00	\$20,000.00	\$20,000.00
2		Incidental	LS	1.00	\$10,000.00	\$10,000.00	\$1,500.00	\$1,500.00	\$12,500.00	\$12,500.00	\$18,000.00	\$18,000.00
3		Traffic Control	LS	1.00	\$4,000.00	\$4,000.00	\$2,640.00	\$2,640.00	\$3,400.00	\$3,400.00	\$2,500.00	\$2,500.00
4		Unclassified Excavation	CY	510.00	\$30.00	\$15,300.00	\$13.40	\$6,834.00	\$25.00	\$12,750.00	\$24.40	\$12,444.00
5		Unclassified Excavation - Digouts	CY	20.00	\$80.00	\$1,600.00	\$80.00	\$1,200.00	\$50.00	\$1,000.00	\$40.00	\$800.00
6		Asphalt Milling	SYD	235.00	\$10.00	\$2,350.00	\$5.90	\$1,386.50	\$9.50	\$2,232.50	\$11.60	\$2,726.00
7		Remove Curb & Gutter	LF	560.00	\$15.00	\$8,400.00	\$4.50	\$2,520.00	\$10.00	\$5,600.00	\$12.80	\$7,168.00
8		Remove Asphalt Pavement	SYD	3,435.00	\$4.00	\$13,740.00	\$4.80	\$16,488.00	\$4.00	\$13,740.00	\$4.40	\$15,114.00
9		Remove PCC Fillet	SYD	55.00	\$35.00	\$1,925.00	\$10.25	\$563.75	\$40.00	\$2,200.00	\$15.70	\$863.50
10		Remove PCC Pan	SYD	16.00	\$35.00	\$560.00	\$35.35	\$565.60	\$50.00	\$800.00	\$18.00	\$288.00
11		Asphalt (PG64-28, Type G1)	TON	1,035.00	\$90.00	\$93,150.00	\$74.00	\$76,590.00	\$73.80	\$76,383.00	\$80.80	\$83,628.00
12		3/4" Base Course	TON	1,330.00	\$30.00	\$39,900.00	\$17.75	\$23,607.50	\$24.90	\$33,117.00	\$25.00	\$33,250.00
13		Curb & Gutter	LF	560.00	\$30.00	\$16,800.00	\$42.00	\$23,520.00	\$37.80	\$21,168.00	\$26.80	\$15,008.00
14		6" PCC Fillet	SYD	55.00	\$100.00	\$5,500.00	\$97.25	\$5,348.75	\$85.00	\$4,675.00	\$92.70	\$5,098.50

15		6" PCC Pan	SYD	16.00	\$100.00	\$1,600.00	\$97.25	\$1,556.00	\$85.00	\$1,360.00	\$92.70	\$1,483.20
16		Adjust Manhole	EA	3.00	\$800.00	\$2,400.00	\$300.00	\$900.00	\$600.00	\$1,800.00	\$650.00	\$1,950.00
17		Adjust Water Valve	EA	1.00	\$200.00	\$200.00	\$150.00	\$150.00	\$200.00	\$200.00	\$450.00	\$450.00
18		Sod	SYD	150.00	\$15.00	\$2,250.00	\$7.50	\$1,125.00	\$9.00	\$1,350.00	\$12.80	\$1,920.00
19		Geogrid	SYD	200.00	\$5.00	\$1,000.00	\$3.75	\$750.00	\$2.75	\$550.00	\$3.90	\$780.00
20		AASHTO T-180	EA	1.00	\$200.00	\$200.00	\$600.00	\$600.00	\$250.00	\$250.00	\$150.00	\$150.00
21		Gravel Filter Sock	LF	80.00	\$6.00	\$480.00	\$3.40	\$272.00	\$5.75	\$460.00	\$5.10	\$408.00
22		Construction Entrance	EA	1.00	\$1,000.00	\$1,000.00	\$2,000.00	\$2,000.00	\$1,000.00	\$1,000.00	\$450.00	\$450.00
TOTAL						\$235,000.00		\$174,892.10		\$202,535.50		\$224,479.20

CITY OF RAPID CITY

I certify that, to the best of my knowledge, this is a true tabulation of bids received for this project.

Todd Peckosh

Todd Peckosh, PE
Project Manager

6/14/17
Date